

APPENDIX A



QUOTATION

Contract 122017-FSC

ACCOUNT	Municipality District of Bonnyville No 87
CONTACT	Will Barefoot
SOURCEWELL NO.:	122017-FSC
DATE	February 15th, 2023

To supply and delivery one (1) new 10 yd³ Vactor 2100i, Single Engine Fan, Dual Stage Combination Sewer Cleaning unit, standard equipped as described below:

Debris Body

10 yd³ Debris Body Capacity
Ex-Ten Steel Cylindrical Debris Tank
Suction Tube Storage, Curbside - 2 Pipe, Rear Door - 2 Pipe
Flat Rear Door w/ Hydraulic Locks and Door Power Up / Power Down / Open / Close
Dual 10" Stainless Steel Float Shut Off System / Rear Mounted in the Body
Double Acting Dump Hoist Cylinder
External Liquid Float Level Indicator
Debris Body Vacuum Relief System
Interior Debris Deflector Plate
60" Dump Height For Dumping In Dewatering Bins
Flat Rear Door w/Hydraulic Open/Close & Locks
Module Paint Wet-on-Wet (DuPont)

Water System

1,300 US Gallons Aluminum Water Tanks
80 GPM @ 2,500 PSI Water System
Multi-Flow Variable Pressure Water System
Performance Package (Hydraulic Variable Flow, Dual PTO's, Dual Hyd Pumps)
Curbside Mounted Water Pump
2" Y-Strainer with 25' Fill Hose
3" Y-Strainer @ Water Pump with 3" Drain Valve
Handgun Assembly with 35' X 1/2" Hose with Quick Disconnects Midship Mounted
Flexible Hose Guide
3 Nozzles with Carbide Inserts With Nozzle Rack and 1" Nozzle Pipe Extension
Water Sight Tubes on Curbside
Water relief valve 1"
Accumulator System for Jet Rodder Water System
Low Water Light With Alarm And Water Pump Flow Indicator (now standard)

Vacuum System

High performance single engine design for productivity in leaf vacuuming/catch basin cleaning / hydro-excavating and sanitary sewer flushing
Two stage - 38" diameter centrifugal compressors
Centrifugal compressor is driven direct through a helical gear type step-up transmission drive with a step-up ratio of 2 to 1
Gear drive is attached directly to the rotor shaft
Gears and bearing are maintained via a splash lubrication system, requiring no manual greasing
Drive system does not utilize pillow block bearings that require excessive daily greasing

QUOTATION

Contract 122017-FSC

Boom System

10' telescopic electric / hydraulic 4-Way boom up, down, left and right
180 Rotation Boom
Remote Wired Pendant Control with 35' Cord
Post Type Front Bumper Boom Storage
Joystick Control for Boom Function – One (1) Front (now standard)

Hose Reel

500' X 1" Piranha Sewer Hose 2500 PSI
15" Hydraulic Telescoping & 270° Rotating Hose Reel with Dual Controls
Hose Reel Manual Hyd Extend/Retract
Hose Wind Guide (Dual Roller)
Hose Footage Counter Located Front Side of Hose Reel – Mechanical
Hose Reel Drive Chain Cover (Full)
Front Mounted Control Including the Following Controls and Gauges:

- Water Pump On / Off with 3 Position Flow Switch
- Chassis Throttle Control
- Boom Joystick Control
- Vacuum Relief Control
- Full Multi-Flow Control
- Chassis Tachometer and Hour meter
- Blower Tachometer and Hour meter
- Hour Meter for Water Pump Operation
- Hour Meter for PTO Operation
- Digital Footage Counter (now standard)
- Digital Water Pressure (now standard)
- Digital Water Flow (now standard)

Electrical & Safety Systems

Colour Coded and Function Heat Stamped Sealed Electrical System
IntuiTouch Electronic Package (New! See attached for additional details)
Circuit Breakers
LED Body Lights - Clearance, Back Up, Stop, Tail & Turn
Electronic Back –Up Alarm
Rear Camera

Mounted on a Western Star Cab and Chassis, subject to Vactor Manufacturing engineering approval and weight distribution study.

OPTION CONTENT:

PART NO.	DESCRIPTION	Order	US List
2110i-SE2	2100i Single Engine Fan, Dual Stage, 10 yrd Debris, Combo	1	\$ 300,009.00
2016i	Additional Water, 1300 Gal Total	1	\$ 3,286.00
1003i	Debris Body Washout	1	\$ 1,851.00
1008i	6" Rear Door Knife Valve w/Camloc, 3:00 position	1	\$ 1,481.00
1014i	Centrifugal Separators (Cyclones)	1	\$ 6,471.00
1015PA	Folding Pipe Rack, Streetside, 8" Pipe	1	\$ 1,285.00
1015i	Folding Pipe Rack, Curbside, 8" Pipe	1	\$ 1,285.00
1022i	Rear Door Splash Shield	1	\$ 1,885.00
1023i	Lube Manifold, with Lube Chart	1	\$ 2,800.00
2006P	Air Purge	1	\$ 1,585.00



QUOTATION

Contract 122017-FSC

2020P	6" Gravity Fill Port on Water Tank	1	\$	1,075.00
3020P	Digital Water Level Indicator	1	\$	825.00
3021P	Digital Debris Body Level Indicator Tied to Vacuum Relief	1	\$	1,106.00
4015P	180 deg. 10ft Telescoping Boom	1	\$	18,728.00
4022PA	Telescoping Boom Elbow, Hard Hat Style	1	\$	554.00
5008PB	Cold Weather Recirculator, PTO Driven, 25 GPM	1	\$	2,103.00
5023P	FanFlushout System	1	\$	612.00
5021PC	Hydro Excavation Kit - Includes Lances, Nozzles, Storage Tray, and VacuumTube	1	\$	3,188.00
6001PB	500' x 1" Piranha Sewer Hose 2500 PSI in lieu of STD	1	\$	596.00
6004PA	Hose Wind Guide (Dual Roller), Auto, Non-Indexing with Pinch Roller	1	\$	4,081.00
6012P	Lateral Cleaning Kit w/150' Hose and Nozzle, 25 GPM/2000 PSI	1	\$	3,693.00
6019P	Rodder Pump Drain Valves	1	\$	600.00
6030P	Heated Handgun Cabinet	1	\$	8,417.00
6031P	Front Hose Reel Storage	1	\$	360.00
8001PJ	Rear Directional Control, LED Arrowboard	1	\$	3,112.00
8002PA	Waterproof, Rechargeable, Wireless, Handheld, LED Spot Light w/12V Charger and Plug	1	\$	435.00
8004PD	Rear Mounted, LED Beacon Light	1	\$	1,205.00
8004PE	Front Mounted, LED Beacon Light	1	\$	1,205.00
8020PL	14 Light Package, 14 Federal Signal Strobe Lights, LED	1	\$	3,944.00
8028P	Worklights (2), LED, Telescoping Boom	1	\$	966.00
8029P	Worklights (2), LED, Rear Door	1	\$	784.00
8029PA	Worklight, LED, Operators Station	1	\$	719.00
8029PB	Worklight, LED, Hose Reel Manhole	1	\$	719.00
8029PC	Worklight, LED, Curb Side	1	\$	713.00
9021PA	Camera System, Front and Rear	1	\$	912.00
9023PA	Safety Cone Storage Rack - Post Style	1	\$	198.00
9023PC	Additional Safety Cone Storage Rack - Post Style	1	\$	198.00
9070PB	Long Handle Tool Storage	1	\$	422.00
	One full width storage box sealed and lockable behind the cab with adjustable shelf shall be pro	1	\$	7,918.75
R40094	Water Heater Prep Kit	1	\$	5,150.00
SUBTOTAL:				\$ 396,476.75
CHASSIS MODIFICATION FEE:				\$ 2,875.00
SOURCEWELL DISCOUNT -3%:				-\$ 11,894.30
SUBTOTAL (US DOLLARS):				\$ 387,457.45
EXCHANGE RATE (37%):				\$ 143,359.26
2023 WESTERN STAR:				\$ 173,073.00
FREIGHT / BROKERAGE:				\$ 7,900.00
PDI / CUSTOMIZED WORK (800,000 BTU WATER HEATER):				\$ 21,010.00
STORM AND SANITARY NOZZLE PACKAGE:				\$ 19,529.00
TOTAL PRICE:				\$ 752,328.70
LOYALTY DISCOUNT:				-\$ 3,767.10
TOTAL PURCHASE PRICE:				\$ 748,561.60

Terms & Conditions

Quotation valid for 14 days

Pricing is in Canadian Dollars

FOB: Bonnyville, AB

Lead Time: TBD

Payment Terms: Net 30 Days from Receipt of Unit

We appreciate the opportunity to assist with this equipment requirement and ask that you not hesitate to contact us should you require

Respectfully Submitted,

Jay McLean
Regional Sales Manager



**Joe Johnson
Equipment**

Subsidiary of General Supply Corporation

Sourcwell
Procurement

Awarded Contract

QUOTATION

Contract 122017-F5C

Joe Johnson Equipment

Cell: (587) 337-5979

jmclean@jjei.com